Sl No.	SPECIFICATIONS	No	L	B	D	QTY	UNIT	RATE (Rs.)	AMOUNT (Rs.)
11.4	Providing and fixing circular 8 guage wire net dust bin of diameter 0.60 m with a height of 1.2 m, along with the circular bottom net of 0.6 m dia, including MS flats of 1.2m length and 1 inch width for vertical joint welding, MS flat 1.9m length and 1 inch width for top and bottom edges and MS flat of 2m length and 3/4 inches width for edges of net shutter with latch arrangement having two hinges with a wirenet of size 1 inch x 1 inch fixed in concrete bed, including 2 coats of approved paint over one coat of primer including cost of all materials, transportation, labour, curing complete as per drawing and directions of Engineer-in-charge **CE approved Rate**	25				25	no	2050	51,250
11.5	Providing and fixing 20 guage M.S. sheet circular dust bin with bottom perforated sheet 450mm dia and 600mm depth, with stands hollow pipes 32mm dia of depth 1.5 m, top cover MS sheet 900x600 mm above the dust bin, horizontal braces 10mm dia bar and revolving system and locking arrangements etc, fixing in concrete bed including 2 coats of approved paint over one coat of primer, including cost of all materials, transportation, labour, curing complete as per drawing and directions of Engineer-in-charge **CE approved Rate**	25				25	no	2750	68,750
11.6	Miscellanous & rounding off								622
						Sub-Total Amount			**1,418,822**
	(Rupees Seven Lakhs EightyTwo Thousand only)								

Scanned by CamScanner

Est. 12	*Installing Shredder & chopping machine with shelter*								
Sl No.	*SPECIFICATIONS*	*No*	*L*	*B*	*D*	*QTY*	*UNIT*	*RATE (Rs.)*	*AMOUNT (Rs.)*
12.1	KSRB 2-2.1 : Earthwork excavation for foundation of buildings, culverts, watersupply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil; clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. Specification No. KBS 2.1 (a) / 2.3.5 (P W D BCSR 2014-15, P-5 I-2.3)								
	long wall	2	8.23	0.90	1.00	14.81			
	short wall	2	5.23	0.90	1.00	9.41			
	column	8	1.20	1.20	1.20	13.82			
						38.05	cum	172.78	6,575
12.2	KSRB 4-1.2 : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregtes @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P W D BCSR 2014-15, P-12 I-4.2)								
	long wall	2	8.23	0.90	0.15	2.22			
	short wall	2	5.23	0.90	0.15	1.41			
	flooring	1	8.00	5.00	0.15	6.00			
	flagging	1	34.00	1.20	0.15	6.12			
	column	8	1.20	1.20	0.15	1.73			
						17.48	cum	4970.34	86,892
12.3	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregtes @ 0.459cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintles, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Specification No. KBS 4.1, 4.6 (P W D BCSR 2014-15, P-13, I-4.11)								
	footing	8	1	1	0.3	2.40			
	pedestal	8	0.5	0.5	0.75	1.50			
	column	8	0.230	0.230	4.5	8.28			
						12.18	cum	5952.96	72,507
12.4	KSRB 4-9.2: Providing **TMT bars Fe 500** steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding whereever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and Paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 (P W D BCSR 2014-15, P-17, I-4.46.2)								
	Qty of steel for □120kg/cum of concrete					1.46	tonne	76900.88	112,398

Scanned by CamScanner

Sl No.	SPECIFICATIONS	No	L	B	D	QTY	UNIT	RATE (Rs.)	AMOUNT (Rs.)
12.5	KSRB 4-6.1 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specificaitons. Specification No. KBS 4.6.2 (P W D BCSR 2014-15, P-15, I-4.28)								
	footing	8	4		0.3	9.6			
	pedestal	8	2		0.75	12			
						21.6	sqm	232.14	5,014
12.6	KSRB 4-6.5 : Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of all materials, labour complete as per specificaiton. Specification No. KBS 4.6.2 (P W D BCSR 2014-15, P-16, I-4.32)								
	column	8	0.920		4.5	33.12	sqm	358.28	11,866
12.7	KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in foundation cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 (P W D BCSR 2014-15, P-23, I-5.6)								
	long wall	2	8.23	0.75	0.40	4.94			
	short wall	2	5.23	0.75	0.40	3.14			
	long wall	2	8.23	0.60	0.40	3.95			
	short wall	2	5.23	0.60	0.40	2.51			
						14.54	cum	3765.12	54,733
12.8	KSRB 5.3-3 : Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 (P W D BCSR 2014-15, P-23, I-5.9)								
	long wall	2	8.23	0.45	0.40	2.96			
	short wall	2	5.23	0.45	0.40	1.88			
						4.85	cum	4458.36	21,603
12.9	KSRB 2.3 : Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20 cms. in depth, compacting each deposited layer by ramming after watering with lead upto 50 m. and lift upto 1.5 m. including cost of all labour complete as per specifications. specification. No. KBS 2.9 (PWD BCSR 2014-15, P-6, I-2.10)								
	inside plinth area	1	8	5	0.5	20.00			
	EWE					38.05			
	deduction of SSM & concrete qty					23.80			
						34.25	cum	116.6	3,994
12.10	KSRB 15.1.4 – do – Providing ruled pointing to coursed stone masonry with cement mortar 1:4, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. (P W D BCSR 2014-15, P-109, I-15.4)								
	long wall	2	9.00		0.40	7.20			
	short wall	2	6.00		0.40	4.80			
						12.00	sqm	87.98	1,056

Scanned by CamScanner

Sl No.	SPECIFICATIONS	No	L	B	D	QTY	UNIT	RATE (Rs.)	AMOUNT (Rs.)
12.11	KSRB 4-1.6 ; Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation,plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P W D BCSR 2014-15, P-12, I-4.6)								
	long wall DPC for basement	2	8.23	0.23	0.90	3.41			
	short wall DPC for basement	2	5.23	0.23	0.90	2.17			
	long wall coping BBM	2	8.23	0.23	0.90	3.41			
	short wall coping BBM	2	5.23	0.23	0.90	2.17			
	ISMC Column fixing	8	0.45	0.45	0.45	0.73			
						11.87	cum	5228.98	62,088
12.12	KSRB 6-2.3 : Providing and constructing burnt brick masonry with approved quality of non-modular bricks of standard size of class designation 50 (table moulded) with cement mortar 1:6 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. Specification No. KBS 6.2 (P W D BCSR 2014-15, P-27, I-6.6)								
	long wall	2	8.23	0.23	0.90	3.41			
	short wall	2	5.23	0.23	0.90	2.17			
						5.57	cum	6191.46	34,502
12.13	KSRB 15.3.4:Providing **15mm thick cement plaster in single coat with cement mortar 1:3,** to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. (P W D BCSR. 2014-15, P-109, I-15.9)								
	long wall	4	8.23		0.90	29.63			
	short wall	4	5.23		0.90	18.83			
						48.46	Sqm	171.72	8,321
12.14	KSRB 14.7-1: Providing and laying **flooring with M15 cement concrete 40 mm thick** using broken granite 20mm and down size laid to line and level in one layer and finish with a floating coat of neat cement , including cost of materials, labour, curing, complete as per specifications. Specification No. KBS 14.3 (P W D BCSR. 2014-15, P-98, I-14.8)								
		1	8	5		40	sqm	315.88	12,635
12.15	KSRB 15.12.1Providing Gopi colour washing to new wall surface in two coats with lime and gopi colour of approved quality, to give an even shade after thoroughly brooming the surface to remove all dirt, dust, mortar drops and other foreign matter including cost of materials, labour, complete as per specifications. (P W D BCSR. 2014-15, P-112, I-15.44)								
	long wall	4	8.23		1.15	37.86			
	short wall	4	5.23		1.15	24.06			
						61.92	sqm	9.54	591

Scanned by CamScanner

No.	SPECIFICATIONS	No	L	B	D	QTY	UNIT	RATE (Rs.)	AMOUNT (Rs.)
12.16	KSRB 7.9 : Providing and fixing M.S.grill work for windows and ventilators using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifications. Specification No. KBS 7.12 (P W D BCSR. 2014-15, P-32, I-7.9)								
	weighing 25kg/sqm	2	8.23	25	2.7	1111.05			
		2	5.23	25	2.7	706.05			
	gable portion	2	5.23	25	0.9	235.35			
						2052.45	kgs	98.58	202,331
12.17	Fabrication supplying and erecting M.S. tubular trusses of all spans as per approved drawing & design with prefabricated steel applications using quality material and are durable, reliable and corrosion and abrasion resistant. Welding shall confirm to latest structural welding code. Quality shall be on various parameters like shape, size, design gauge and polish. The entire trusses is anchored in RCC column by using 4 nos of M.S. anchor bolts at each support with 10mm thick base plate and shoe plate. The work includes cutting, straightening, placing in position of M.S. pipes and welding wherever necessary and applying one coat of redoxide primer coat to all the members including cost of all materials, labour charges, and hire charges of machineries for cutting, welding, grinding and erection equipments, with all lead and lift, transportation, letc., complete as per specification (P W D BCSR. 2014-15, P-40, I-7.29)								
	unit weight 3kg/sqm	4	11	5	3.0	660			
	purlin weight 4.40kg/sqm	1	8	5	4.4	176			
	tie weight 0.36kg/sqm	1	8	5	0.36	14.4			
						850.4	kgs	143.1	121,692
12.18	KSRB 8.3-2 : Providing and laying to required line and slope roofing with semi-corrugated (Trafford) asbestos cement sheet 6mm. thick fixed with galvanised iron J or L hooks, bolts and nuts 8mm. dia C.I plain and bitumen washers, over the existing purlins, rafters and trusses including cost of materials, labour, complete as per specifications. (P W D BCSR. 2014-15, P-46, I-8.6)								
		2	9	5		90	sqm	403.86	36,347
12.19	KSRB 8.3-4 : Providing and fixing ridges, hips with asbestos cement sheet roofing with G.I. J or L hooks, bolts and nuts 8mm. dia G.I.plain and bitumen washers, serrated or plain wings, adjustable ridges, including cost of materials, labour, complete as per specifications. (P W D BCSR. 2014-15, P-46, I-8.8)								
		1	9			9	mtr	278.78	2,509
12.20	Shedder Machine made of Mild steel with electrical motor of 5HP three phase,30 No Flat plates cutters, weight of 400kg,handle all type of dry leaves cut upto 10-20mm length crushing rate depending on the type of material including all service tax and installation excluding Electrification.								
	quatation rate	1				1	unit	171750	171,750

Scanned by CamScanner

Sl No.	SPECIFICATIONS	No	L	B	D	QTY	UNIT	RATE (Rs.)	AMOUNT (Rs.)
12.21	Chopper Machine made of Mild steel with electrical motor of 5HPthree phase,20No cutting Knives weight of 400kg,handle all type of organic waste like wet,dry vegetables and Biomass,cut upto 50-150cm length crushing rate,depending on the type of material including all service tax and installation excluding Electrification.								
	quatation rate	1				1	unit	194650	194,650
12.22	Miscellaneous								211
								Sub-Total	1,224,266
	(Rupees Twelve Lakhs Twenty Eight Thousand Only)								

Scanned by CamScanner

Sl. 13

High mast Lamp for Kalyani (16mtr height 8 Lum)

Sl No.	SPECIFICATIONS	No	L	B	D	QTY	UNIT	RATE (Rs.)	AMOUNT (Rs.)
13.1	KSRB 2-2.1 : Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, **in ordinary soil** not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(a) / 2.3.5 (PWD BCSR 2014-15, P-5, I-2.3)	1	2.00	2.00	1.65	6.60	cum	172.78	1140.35
13.2	KSRB 4-1.3 : Providing and laying in position **plain cement concrete of mix 1:4:8** with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregtes @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P W D BCSR 2014-15 P-12, I-4.3)	1	2.00	2.00	0.15	0.60	cum	4757.28	2,854
13.3	KSRB 4.2.2 : Providing and laying in position **reinforced cement concrete of design mix M20** with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.46cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintles, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Specification No. KBS 4.1, 4.6 (PWD BCSR 2014-15, P-13, I-4.11)								
	footing	1	1.80	1.80	0.3	0.97			
	pedestal	1	0.75	0.75	1.5	0.84			
						1.82	cum	5952.96	10,809
13.4	KSRB 4.9.2 : Providing **T.M.T steel reinforcement for R.C.C work** including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 (PWD BCSR 2014-15, P-17, I-4.46)								
	TMT bars Fe 500					0.15	tonne	76900.88	11,171
13.5	KSRB 4-6.1 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, **footings**, bases of columns for mass concrete including cost of all materials, labour complete as per specificaitons. Specification No. KBS 4.6.2 (PWD BCSR 2014-15, P-15, I-4.28)								
	footing	1	7.20		0.3	2.16	sqm	232.14	501

Scanned by CamScanner

Sl No.	SPECIFICATIONS	No	L	B	D	QTY	UNIT	RATE (Rs.)	AMOUNT (Rs.)
13.6	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for **vertical surface** such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specificaitons. Specification No. KBS 4.6.2 (PWD BCSR 2014-15, P-15, I-4.31)								
	pedestal	1	3.00		1.8	5.40	sqm	287.26	1,551
13.7	Fabrication, Supplying, Erection,Testing and Commissioning of 16 mtrs long **polygon hihg mast** with Single / Multiple of **bottom dia 410mm and top dia 150mm** with two telescopic sections having bottom piece 6.50mtrs with 3mm thick and top piece 6.50mtrs 3mm thick as per BSEN 10025 grade S 355 JO steel sheet plate for shaft suitable to withstand a wind velocity of 180kmph as per IS 875 part 3 (as per GA Drawing). Base plate having size 520mm dia, 16mm thick with 6nos. of foundation bolts M24 X 850mm long and connected accessories as per IS ISO 1461 with an average 70 microns as per IS 2629, and welded as per BS 5135 single L - seam joint. The mast, shall have two way head frame with 4nos of 190mm die cast LM -6 pulleys, steel axils, phosphorus bronze bearing bush press fitted with seperate guides for 2 runs of 5mm dia stainless steel wire rope and 5 core 2.5Sqmm EPR insulated PCP sheathed trialling power cable all are housed inside the bottoms of mast with suitable locking 250 x 950mm hinged door. The mast shall have power tool having 0.5HP, 415 V, 50Hz, 3-Phases reversible 960RPM geared motor mast. The mast shall have land turn of 2 segments, 2150mm dia with max load of 250kgs carrying capacity as per IS 1239. The mast shall be erected on existing 1600mm depth of shallow shaft RCC footing. The mast shall be supplied with 3mm thick template, lightning arrester of 1.2m length galvanized pipe with top arrow will be fitted at top of the head frame cover and GLS type aviation twin lamps fitting with wiring complete. excluding foundation) as per technical data. (PWD BCESR 2014-15. P-36, I-5.17.2)								
		1				1	Each	160,000	160,000
13.8	Supplying **High pressure 400 Watts Metal halide flood light luminary** suitable for use with high pressure metal halide lamp with integrated control gear. The fitting shall be non-corrosive high pressure die cast aluminium housing powder coated with toughened and heat resistant glass with low copper content black/grey powder coated paint finish with EPDM gasket. Reflector shall be made of high purity pre-anodized aluminium. Cable entry through a cable gland with toggle clips. IP 65 protection for both and optical and electrical compartment. Bottom cover may be with polycarbonate / tempered / toughened glass. Luminaire efficiency should be >60% and ambient temperature >35 deg C. High intensity discharge Electro magnetic ballast with copper winding of Octocyclic winding coil. Class H insulated dual coated copper wire. Compliance to IEC 61347-2-9 Safety and IEC 60923-performance. Winding temperature for HID ballast tw = 130 deg C and temperature rise ?T - 70 deg C. Luminaire shall be suitable to operate on 230/250 Volts 50Hz AC supply finish including wiring, ignitor,condensor. SS toggles for opening front hingeable glass, prewir ed to terminal block (PWD BCESR 2014-15. P-23, I-4.18.3) **8arms x 1nos of each arm=8nos**								
		8				8	Each	10,311	82,488
13.9	Bescom deposit						LS		200,000
13.10	Miscellaneous								485
							Sub-Total		**471,000**
	(Rupees Four Lakhs SeventyOne Thousand Only)								

Scanned by CamScanner

Sump-tank

No.	SPECIFICATIONS	No	L	B	D	QTY	UNIT	RATE (Rs.)	AMOUNT (Rs.)
4.1	KSRB 2-2.2 : Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, **in hard soil** not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(b) / 2.3.5 (P W D BCSR. 2014-15, P-5, I-2.4)								
		3	3.4	2.4	1.5	36.72	Cum	259.7	9,536
14.2	KSRB 4-1.2 : Providing and laying in position **plain cement concrete of mix 1:3:6** with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregtes @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P W D BCSR. 2014-15. P-12. I-4.2)								
		3	3.4	2.4	0.2	4.896	Cum	4970.34	24,335
14.3	KSRB 4.2.2 : Providing and laying in position **reinforced cement concrete of design mix M20** with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.46cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintles, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Specification No. KBS 4.1, 4.6 (P W D BCSR. 2014-15, P-13, I-4.11)								
	top and bottom slab	6	3.2	2.2	0.15	6.34			
	wall	3	10.4	0.2	1.3	8.11			
						14.45	Cum	5952.96	86,008
14.4	KSRB 4.9.2 : Providing **T.M.T steel reinforcement** for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 (P W D BCSR. 2014-15 P-17, I-4.46.2)								
	TMT bars Fe 500					1.16	tonne	76900.88	88,885
14.5	KSRB 4-4.1 : Extra for use of water proofing compound in Cement concrete of mix M25,at one kg of compound per bag of cement. Specification No. KBS (P W D BCSR. 2014-15, P-14, I-4.24)								
	item no 7.3 qty taken					14.45	Cum	270.3	3,905
14.6	KSRB 15.3.3Providing **12mm thick cement plaster** in single coat with cement mortar 1:6, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.(P W D BCSR. 2014-15, P-109, I-15.11)								
	pit earth surface	3	11.2		1.2	40.32	Sqm	140.98	5,684

Scanned by CamScanner

Sl No.	SPECIFICATIONS	No	L	B	D	QTY	UNIT	RATE (Rs.)	AMOUNT (Rs.)
14.7	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work **for vertical surface** such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specificaitons. Specification No. KBS 4.6.2 (P W D BCSR. 2014-15, P-15, I-4.31)	3	10		2.25	67.5	Sqm	287.26	19,390
14.8	KSRB 4-6.2 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work **for flat surface** such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specificaitons. Specification No. KBS 4.6.2 (P W D BCSR. 2014-15,P-15, I-4.29)	3	3	2		18	Sqm	308.46	5,552
14.9	KSRB 4-6.9 :Providing and removing centering, shuttering, strutting, propping etc., **for edges of slabs** and breaks in floor, cills, plinth including cost of all materials, labour complete as per specificaiton. Specification No. KBS 4.6.2 (P W D BCSR. 2014-15, P-16, I-4.36)	3	11.2		0.2	6.72	Sqm	685.82	4,609
14.10	KSRB 15.3.4:Providing **15mm thick cement plaster in single coat with cement mortar 1:3,** to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.(P W D BCSR. 2014-15, P-109, I-15.9) internal	3	10.4		2.25	70.2	Sqm	171.72	12,055
14.11	KSRB15-4.1 Extra for providing and **mixing waterproofing compound** in cement plaster work at one kg per bag or in the proportion recommended by the manufacturers, for cement mortar 1:3, 12mm thick cost of materials complete as per specifications. (P W D BCSR. 2014-15,P-110, I-15.23)	3	10.4		2.25	70.2	Sqm	9.01	633
14.12	KSRB 12-6.3 : Providing **cast iron footrest** and fixing in manhole with M 10 cement concrete block of 20x20x10cms, using 20mm and down size metal of size including cost of materials, labour charges, curing complete as per specifications. Specification No. KBS 12.4.6 (P W D BCSR. 2014-15 P-70, I-11.46)	9				9	nos	231.08	2,080
14.13	Manhole cover PWD BCSR 2012-13 P-XXXVIII, 18" x 24" 38kg	3				3	nos	2015.06	6,045
14.14	KSRB13-3.4: Providing and fixing in trenches galvanised / mild steel tubes (medium grade) 32mm dia nominal bore with all fittings (earth work in trenches to be measured and paid for separately) including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications. Specification No.KBS 13.2.14 / 13.6 (P W D BCSR. 2014-15 P-87, I-13.13)								
	32mm dia	1	5			5	mtr	316.94	1,585
14.15	KSRB13-4.1 : Making connection of G.I distribution branch with G.I main of 25 to 40mm. nominal bore, including cutting and threading the pipes, providing and fixing Tee, nuts, labour for all item of works, testing and HOM of equipments complete as per specifications. Specification No.KBS 13.10 (P W D BCSR. 2014-15,P-88, I-13.20)	1				1	nos	351.92	352

Scanned by CamScanner